

<b>Compost Education Centre Greenhouse Budget</b>				
<b>Castle Building</b>	<b>per piece</b>	<b># of pieces</b>	<b>total</b>	<b>Function</b>
2x6x12 cedar	22.99	4	91.96	base
2x4x8 cedar	7.89	10	78.9	end framing
2x4x12 cedar	12.99	1	12.99	roofline
1/2" rebar (20' length)	5.5	2	11	foundation, cut into 4' lengths
lathe			20	securing plastic
clamps			15	securing ends of hoops
metal strapping			5	securing rebar to frame
screws			20	screwing frame together
nails			5	nailing lathe
hinges			10	for door*
<b>West-Tech Irrigation Supply</b>				
Schedule 40 PVC 1", 20 ft	23.15	5	115.75	hoops
Schedule 40 PVC 1", 10 ft	1	1	13.23	2' hoop extension
Schedule 40 PVC 3/4", 20 ft	15	2	30	side hoops (extra support)
<b>Home Hardware</b>				
acrylic spray paint	8	4	32	spray hoops to protect plastic
<b>B&amp;W Greenhouses</b>				
AC plastic	148.42		148.42	
<b>Total</b>			<b>609.25</b>	

\* cost for wood door will vary